


REV	DATE	MODIFICA	DRAWER
0	23/01/2009	FIRST ISSUE	S.B.



Material List of Drw: 12834 - 5557

Title: HORIZONTAL SHEAVE ON TROLLEY - ASSEMBLY-

Ref. Drv 12834 - 5000 Ref. Pos: 11

Item\Fam: 0600 Groups for crane: 2

Material Handling Engineering																	
<div><div><div>Data: 03-lug-09</div><div>Project: 12834</div><div>Job: 18033</div><div>Mat List of Drw: 5557</div><div>Ref. Drw: 5000 - 12834</div><div>Ref. Pos: 11</div><div>Item\Fam : 0600</div><div>Groups for crane: 2</div></div><div><div>Customer: PIRAEUS PORT AUTHORITY - RMG 40t</div><div>Title: HORIZONTAL SHEAVE ON TROLLEY -ASS</div></div></div>																	
POS	DRW N°	ELECTRICAL CODE	DESCRIPTION	MATERIAL	NOTE FUNCTION	DIMENSIONS	Qty in Drw	Weight in Drw	Qty for 1 Crane	Qty for Job	RAM	ORD	SUPPLIED BY	MADE BY	ITEM	FAM	REV
1	12834 - 907		SHEAVE DIA560	SEE DWG.		DIA 560	1	70	2	16			OMG		06		16
2	12834 - 5558		FRAME	S 355 JO or equivalent			1	90	2	16					06		82
3	12834 - 5552		PIN	C 45 E +N - EN 10083-1		DIA110x228	1	14,2	2	16					06		82
5	12834 - 5554		COVER	S 235 JR or equivalent		DIA110x12	1	0,9	2	16					06		82
6	12834 - 5555		COVER	S 235 JR or equivalent		DIA125x12	1	1,2	2	16					06		82
7	12834 - 5557		SCREW	A4 S.S. AISI 316		M10x40 DIN931/ISO4014	6		12	96					06		81
8	12834 - 5557		WASHER	A4 S.S. AISI 316		A11 DIN127	6		12	96					06		81
WEIGHT FOR CRANE [kg]: 352,6																	