



| Cable Reel 20 KV- Technical Features | | | | | |
|---|---|------|----------|-----------------------|-----------------|
| s/n | Description | Unit | Quantity | Unit price | Total price (€) |
| 1 | M.V. CABLE REEL 20KV, EL12/20KV 3*35+2*25/2+6FOX62,5/125 [(N)TSCGEWÖU 3x35+2x25/2+6FOX62,5/125 12/20KV MULTI-MODE FIBEROPTICS)] Supply of two (2) separated cable drums of 360 m each | m | 720 | | 0,00 |
| | | | | Total: € | 0,00 |
| | | | | Plus VAT 24%: € | 0,00 |
| | | | | GRAND TOTAL: € | 0,00 |
| Remarks & General Terms | | | | | |
| <p>1. The cable is intended for QCs and RMGs and will be delivered, accompanied by a CD which will contain i.e. VLF test measurements regarding insulation, continuity of each cable reel, issued by the manufacturer.</p> <p>International standards & guide</p> <ul style="list-style-type: none"> • DIN VDE 0276 (after laying tests on new cables) • IEC 60502-2:2014 Cables for rated voltages from 6 kV (Um = 7,2 kV) up to 30 kV (Um = 36 kV) (after laying tests on new cables) • IEEE 400-2012 Guide for Field Testing and Evaluation of the Insulation of Shielded Power Cable Systems • IEEE 400.2-2013 Guide for Field Testing of Shielded Power Cable Syst. Using Very Low Frequency (VLF) • CENELEC HD620 S1 (after laying tests on new cables) | | | | | |
| <p>2. Delivery Terms: i. DAP: PPA Warehouse, Androutsou & Kanari - Drapetsona, Piraeus (next to the Firestation) ii. The delivery time of all items has to be clearly stated within the offer. Delivery Time: as soon as possible (urgent procurement).</p> | | | | | |
| <p>3. Payment Terms: Payment within two (2) months upon invoicing and only after the products' final delivery and acceptance by the competent Acceptance Committee.</p> | | | | | |